

BIDS AND AWARDS COMMITTEE

Supplemental Bid Bulletin No. 2
August 23, 2017

Supply, Delivery, and Installation of Security Surveillance in the DOF

This Supplemental Bid Bulletin No. 2 is issued to modify or amend the item in the Bid Documents. This shall form an integral part of the Bid Documents.

REFERENCE		AMENDMENT/CHANGE/CLARIFICATION	
<i>Section VI. Schedule of Requirements</i>			
Description	Quantity	Description	Quantity
Camera DC-Y 1513W 5MP 360 Fisheye Camera DC-D1223R 2MP Full HD IR Indoor Dome Camera DC-F1211 (a) 2MP Full HD Indoor flat Dome Camera DC-S1283WRX 2MP Full HD PTZ outdoor Camera DC-T1234WR Full HD IR Bullet Camera	 56 51 3 1 3	Camera 5MP 360 Fisheye Camera – Functionality 2MP Full HD IR Indoor Dome Camera 2MP Full HD Indoor flat Dome Camera 2MP Full HD PTZ outdoor Camera Full HD IR Bullet Camera or Equivalent	 56 51 3 1 3
Network Video Recorder DR-8364-S up to 64 ch NVR 2 GIGA LAN	 3	Network Video Recorder Up to 64 ch NVR 2 GIGA LAN	 3
Accessories DE-1108 – DirectIP 8 channelencoder DA-ES-1104 e – SATA Storage 4 Bay Rack DH-2128PF DirectIP 28 port Gigabit PoE switch	 1 1 9	Accessories SATA Storage 4 Bay Rack 28 port Gigabit PoE switch	 1 1 9
VMS Software IDIS Center: Video Management Software	 6	VMS Software Video Modify Management Software	 6
Monitor Western Digital HDDs	 24	Monitor HDDs	 24

Enterprise Series 6TB 40" LED Monitor	3	Enterprise Series 6TB 40" LED Monitor	3
--	---	--	---

Section VII. Technical Specifications

<p><u>Camera</u> DC-Y1513W 5MP 360 Fisheye Camera Roof Deck – 4 units 7th Floor – 14 units 6th Floor – 3 units 5th Floor – 7 units 4th Floor – 6 units 3rd Floor – 6 units Podium – 10 units Basement – 6 units</p> <p>DC-D1223R 2MP Full HD IR Indoor Dome Camera Roof Deck – 4 units 7th Floor – 6 units 6th Floor – 9 units 5th Floor – 4 units 4th Floor – 6 units 3rd Floor – 5 units Podium – 5 units Basement – 12 units</p> <p>DC-F1211(A) 2MP Full HD Indoor Flat Dome Camera For Elevators – 3 units</p> <p>DC-S1283WRX 2MP Full HD PTZ Outdoor Camera Front Gate – 1 unit</p> <p>DC-T1234WR Full HD IR Bullet Camera Perimeter Areas – 3 units</p> <p><u>Network Video Recorder</u> DR-8364-S up to 64 Ch NVR 2 GIGA LAN – 3 units 6 Bay rack type 8bay x 6tb = 48 tb capacity (HDD not included) with two (2) SPF ports for fiber optic line</p> <p><u>Accessories</u> DE-1108 – DirectIP™ 8-channel Encoder – 1 unit Integration for the existing 8 analog cameras</p> <p>DA-ES1104 e-SATA Storage 4 Bay rack mount – 1 unit 4 eSATA x 4 bay x 6tb hdd (Up to 6TB capacity each) total of 96tb</p>	<p><u>Camera</u> 5MP 360 Fisheye Camera Roof Deck – 4 units 8th Floor – 1 unit 7th Floor – 14 units 6th Floor – 3 units 5th Floor – 7 units 4th Floor – 6 units 3rd Floor – 6 units Podium – 10 units Basement – 6 units</p> <p>2MP Full HD IR Indoor Dome Camera Roof Deck – 4 units 7th Floor – 6 units 6th Floor – 9 units 5th Floor – 4 units 4th Floor – 6 units 3rd Floor – 5 units Podium – 5 units Basement – 12 units</p> <p>2MP Full HD Indoor Flat Dome Camera For Elevators – 3 units</p> <p>2MP Full HD PTZ Outdoor Camera Front Gate – 1 unit</p> <p>Full HD IR Bullet Camera Perimeter Areas – 3 units</p> <p><u>Network Video Recorder</u> Up to 64 Ch NVR 2 GIGA LAN – 3 units 6 Bay rack type 8bay x 6tb = 48 tb capacity (HDD not included) with two (2) SPF ports for fiber optic line (2 months recording)</p> <p><u>Accessories</u> 8-channel Encoder or equivalent – 1 unit Integration for the existing 8 analog cameras</p> <p>Storage 4 Bay rack mount or equivalent – 1 unit 4 eSATA x 4 bay x 6tb hdd (Up to 6TB capacity each) total of 96tb</p>
---	---

DH-2128PF DirectIP™ 28-port Gigabit PoE Switch – 9 units 2 copper port 2 sfp port	28-port Gigabit PoE Switch – 9 units 2 copper port 2 sfp port
<p><u>VMS Software</u> IDIS Center: Video Management Software – 6 clients Live view / Record / Playback / Remote Access / Backup</p> <p><u>Monitor and HDD (Can be purchase separately)</u> Western Digital HDDs Enterprise Series (6TB) – 24 units Need eight (8) units for storage requirement</p> <p>40” LED Monitor – 3 units For live viewing, playback and spot monitoring</p> <p><u>Labor Cost</u> Estimated Costing – 1 lot (Cable pulling, termination, testing, commissioning and programming)</p>	<p><u>VMS Software</u> Video Management Software – 6 clients Live view / Record / Playback / Remote Access / Backup</p> <p><u>Monitor and HDD (Can be purchase separately)</u> HDDs Enterprise Series (6TB) – 24 units Need eight (8) units for storage requirement</p> <p>40” LED Monitor – 3 units For live viewing, playback and spot monitoring</p> <p><u>Labor Cost</u> Estimated Costing – 1 lot (Cable pulling, termination, testing, commissioning and programming)</p> <p><u>Training Warranty</u> after sales service – 3 years</p>
	The schedule on the submission of bids is August 31, 2017, 9:45 a.m. at the BAC Secretariat. Opening of bids is at 11:00 a.m. at the DFG Room.

For guidance and information of all concerned.

GIL S. BELTRAN
Undersecretary and
BAC – Chairman